

FEB 22 1996  
COMMISSION

GRATIOT COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.  
RECORDED

'95 DEC 20 PM 1 28

Corner in \_\_\_\_\_  
 Located In: \_\_\_\_\_  
 Corner Code # \_\_\_\_\_

Gratiot  
 (County)

Sumner Township

Public Land Survey Sec 18 T 11 N R 4 W A-6, W 1/4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

*Janet M. Davis*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Tingley a field survey on April 11, 1995,  
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:  
 Not set by GLO  
 -871, S.S. Hastings, Deputy County Surveyor, Liber B, page 177, Record of Minutes of Survey in Gratiot  
 County Road Commission's Office  
 Beech 10" N06°E 32-1/2 links  
 Beech 12" S86°E 24 links  
 -879, S.S. Hastings, County Surveyor, Liber C Page 269, Record of Minutes of Survey  
 Stone and Earthenware  
 Beech 12" S86°E 24 links  
 Map shows 1.14-1/2 chains North of Corner for 11-5  
 Also Liber C Page 33, Liber B 177

ACCEPTED BY THE GRATIOT COUNTY SURVEY FEE GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

*WGT*  
William Tingley, PS, Chairman

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found a large stone 0.5 feet x 1.6 feet (length unknown) shaped like a grave marker and found a 0.3 foot x 0.8 foot  
 pointed stone with crockery. Set a capped iron rod between stones. Located on the Eastside of a N-S ditch  
 and 12 feet North E-W ditch on the Westside of a N-S two track road. Also of a E-W wire fence.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set Stone and Capped Iron #30104. Stone too close to set Standard Remonumentation Corner.  
 Set Nail and Tag in Eastside of 20" Maple South 37.92 feet  
 Set Nail and Tag in Northside of 6" Oak N45°E 34.37 feet  
 Set Nail and Tag in Southside of 6" Poplar S70°E 34.34 feet  
 Set Nail and Tag in Westside of 6" Ash S45°E 34.13 feet

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by William Tingley Date 12 7 2 1995  
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

