

FEB 22 1996

GRATIOT COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH. RECORDED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 20 PM 1 28

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

or corners in
Gratiot
 (County)

Located In: Sumner Township

Corner Code # B-5, 1/4 Corner

Public Land Survey Sec 7 T 11 N R 4 W
 T _____ R _____
 T _____ R _____
 T _____ R _____

Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Lot No. _____, Recorded Plat _____
 Private Claims _____

William Tingley a field survey on April 11, 1995,
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 832, Orange Risdon, Deputy Surveyor, GLO Notes
 Set Quarter Section Post
 White Oak 18" N54°W 3 links
 Maple 18" S54°E 3 links
- September 26, 1871, S.S. Hastings, Deputy County Surveyor, Liber I, Page 348-349, Gratiot County Records
 Stake between logs of causeway; Notch cut in pine log
 Black Ash 22" N66°W 63-1/2 links
 Sugar Maple 4" S57-1/2°E 71 links
- May 1879, S.S. Hastings, Field Book, 11-4, Page 98-99
 Corner on causeway
 Black Ash 22" N66°W 63-1/2 links
 Maple 4" S57-1/2°E 71 links
- July 1879, S.S. Hastings, Field Book 11-4
 Same as Above
- 1879, S.S. Hastings, Minutes of Survey Book County Drain Commissioner's Office
 Section 8, same record as above with additional witness
 Pine Stump 36" S76°E 1.06 chains
- 1992, Gratiot County Road Commission
 found 2 foot long stake with stones

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Round Woodstake in Notch of Old Causeway logs

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95.

WGT
 William Tingley, PS, Chairman

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner Over Stake in Monument Box
- Northwest Corner Concrete Curb N30°W 59.97 feet
- Southeast Corner Concrete Curb S30°W 73.30 feet
- Southwest Corner Concrete Curb S75°W 59.95 feet
- Set Nail & Tag in Northeast side of Power Pole S45°E 142.97 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-12, 1995
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

