

FEB 22 1996

GRATIOT COUNTY REMONUMENTATION PROGRAM

GRATIOT CO. MICH. RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 20 PM 1 28

For corners in Gratiot Located In: Sumner Township Corner Code # _____
 (County)

1. Public Land Survey Sec 18 T 11 N R 4 W B-7, 1/4 Corner
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	19	20	21	22	23	24							
8													
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on April 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1832, Orange Risdon, Deputy Surveyor, GLO Notes
Set quarter section post
Black Ash 18" N34°E 36 links
Black Ash 10" S42°W 26 links
- September 1871, S.S. Hastings, Deputy County Surveyor, Liber A, Page 348, Gratiot County Records
Stake on Corner
Black Ash 10" N36-1/4°W 44 links
Black Ash 16" S40°E 42 links
- September 1879, S.S. Hastings, Field Book 11-4, pages 122-123
Cedar 2 x 2 covered with brick and crockery
Black Ash 14" N81°W 67-1/2 links
Black Ash 2" N74°E 41 links
- May, 1897, S.S. Hastings, Field Book, 11-4, Pages 122-123
Kingbolt and crockery
Elm 5" S69°E 40 links
- July 1879, S. S. Hastings, County Surveyor, Liber C, Page 33 and 34
See previous Liber A & B
Some bricks buried
- 1907, F.W. Hastings recorded Book D, Page 90, Record of Minutes of Survey in Gratiot Drain Commissioner's Office
Kingbolt and crockery
Elm 5" S69°E 40 links
- September 1907, F.W. Hastings, County Surveyor, Record of Minutes of Survey, Liber D, Page 90-91
Corner Found, iron Kingbolt, stones on top, stone broken crockery and brick around Elm 5" S69°E 40 links

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95

WGT
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found King Pin in nest of bricks in a notch in pine, 3.6 feet below surface, raised with Remonumentation Corner in the Centerline of a North-South Road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner over King Pin.
- Set Nail and Tag in the Southside 12" Maple East 54.46 feet
- Set Nail and Tag in the Southeast side 10" Maple S40°W 62.57 feet
- Set Nail and Tag in Southside 8" Maple S80°W 37.73 feet
- Set Nail and Tag in the Southside of a clump of 5" Maples N45°E 76.49 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-12, 1995
 Surveyor's Michigan License No. 30104

