

REMONUMENTATION

FEB 22 1996
COMMISSION

GRATIOT COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.
RECORDED

'95 DEC 20 PM 1 28

Janet M. Davis
REGISTER OF DEEDS

For corners in Gratiot Located In: Sumner Township Corner Code # _____
(County)

1. Public Land Survey Sec 9 T 11 N R 4 W E-5, Sec Cor
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on October 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1832, Orange Risdon, Deputy Surveyor, GLO Notes
Set Post Corner Sections 8, 9, 16 & 17
Pine 18" S58°E 10 links
Pine 30" N49°W 54 links
- 1876, D.W. Altenburg, County Surveyor, Field Book 11-4, Page 100-101
Pine root - old corner found
Government Pine Witness N49°W 54 links
Notch in Stump Fence N46°E 75-1/2 links
- 1879, S.S. Hastings, County Surveyor, Book C, Page 34, Record of Minutes of Survey in County Drain Commissioner's Office
Pine Stump 20" S58°E 10 links
Pine Stump 30" N49°W 54 links
- Field Book 11-4, Pages 109-110
Same record as above
- 1879, S.S. Hastings, County Surveyor, Liber C, page 35-36
Same as above
- March 1974, David B. Whittier, #10070 in LCRC, Liber 1, Page 245
Found 1-1/4" Pipe
Southwest to 2" Round Steel Post 73.63 feet
Northwest to 1-1/4" Round Fence Post 40.85 feet
Southeast to centerline Telephone Junction Box 36.90 feet
- 1992, Gratiot County Road Commission
Found 1" Shaft with many 4" stones around
2" Iron Anchor Post (face) S45°W 39.85 feet
6" Wood Anchor Post (face) N45°W 46.50 feet

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11-29-95


W. Tingley
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner found. 1/2" pipe over 1" shaft. Centerline of Intersection of N-S Gravel Road and E-W Gravel Road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Remonumentation Corner in Monument Box over 1" shaft and 1/2" pipe

- Stop Sign Post Southeast 35.1 feet
- Stop Sign Post Northwest 33.8 feet
- 15" CMP N45°W 43.8 feet
- 15" CMP N45°E 41.7 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by William G. Tingley Date 12-22-1995
Surveyor's Michigan License No. 30104