

**SURVEY &
REMONUMENTATION**

1993

LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH.
RECORDED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 20 PM 12 24

For corners in Gratiot Gratiot County Remonumentation Program
(County) Located in: Corner Code #

Janet M. Davis
REGISTER OF DEEDS

- 1. Public Land Survey Sec. 32 T 11 R 4 E-13, SE cor
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on October 23, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 April 20, 1831 R. Clark, Jr., Deputy Surveyor
 Set post corner Section 32 and 33 T11N R4W
 Beech 8" N18°E 20 links
 Beech 7" N37-1/2°W 29 links
 March 12, 13, 14, 1888 D.W. Altenburg, County Surveyor, Book C, Page 148, from
 Record of Minutes of Survey in Gratiot County Drain Commission Office
 Found small stone
 Red Oak 8" S9°W 22-1/2 links
 Pine Stump 36" S77-1/2°W 1.49-3/4 chains
 Post 1/4 corner Section 5 T10N R4W West 3.86-3/4 chains
 1896 W.L. Altenburg, County Surveyor, Book C, Page 200-219, from Record of Minutes of
 Survey in Gratiot County Drain Commission Office
 Found Square head bolt 1' deep
 Maple 6" N45°E 96.7'
 Oak 30" S09°W 14.75'
 Maple 15" N20°E 133.45'
 July 2, 1981 John Nelson, #21278, Liber 2, Page 35 of Land Corner Recordation Book
 Found Square head bolt 1' deep raised with 5/8" rerod with cap.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Accepted as corner. Found 5/8" rerod over square head bolt by John Nelson, as recorded in Liber 2, page 35 in Land Corner Recordation Book.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set remonumentation corner in monument box 1' North of Centerline of County Road 555.
- Set nail with registered land surveyor tag in East side of fence post North 49.50'
- Set nail with registered land surveyor tag in West side of 28" White Oak N30°E 133.40'
- Set nail with registered land surveyor tag in Southwest side of Power Pole S62°E 116.41'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by William J. Tingley Date November 30, 1993
Surveyor's Michigan License No. 30104