

1993

LAND CORNER RECORDATION CERTIFICATE

GRATIOT CO. MICH. RECORDED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970 Gratiot County Remonumentation Program

'93 DEC 20 PM 12 24

For corners in GRATIOT (County)

Located In: Corner Code #

- 1. Public Land Survey Sec. 34 T 11 R 4 G-13, SW cor
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Janet M. Davis REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on October 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found, as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- April 20, 1831 Robert Clark, Jr. Deputy Surveyor 80 chains, set post corner Sections 33 and 34 Beech 6" N26°E 18 links Beech 10" N29°W 27 links
January 25, 26, 27, 1875 D.W. Altenberg, County Surveyor, Book B, Page 125 from Record of Minutes of Survey of Gratiot County Drain Commission
1885 S. S. Hastings, Deputy County Surveyor, Book C, Page 141 from the Record of Minutes of Survey of Gratio County Drain Commission
November 28, 29, 1892, S. S. Hastings, Deputy County Surveyor, Book C, Page 141 from the Record of Minutes of Survey of Gratiot County Drain Commission
March 30 - 31, 1896, D.W. Altenburg, County Surveyor, Book C, Page 200 from Record of Minutes of Survey of Gratiot County Drain Commission
July 2, 1981 John Nelson, #21273, Liber 2, Page 18 of Land Corner Recordation Book

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 5/8 Re-rod and Cap 0.8' North of East Road by John Nelson, #21273, Liber 2, Page 18 of Land Corner Recordation Book.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set remonumentation corner in mon box 0.8 feet North of Centerline Road, 286.95' East of North 1/4 Corner, Section 4, T10N, R4W

- Nail and tag West Side of Power Pole S5°W, 53.67'
Nail and tag Northwest Side of Fence Post S48°W 27.57'
North 1/4 Corner Section 4, T10N, R4W 5/8" Rerod with cap N85°W 286.95'
Nail and tag in West Side of 14" Ash N4°W 45.13'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G Tingley Date November 30, 1993 Surveyor's Michigan License No. 30104

Table with 13 columns (A-M) and 13 rows (1-13) containing numbers 1-36 in a grid pattern.

