

SURVEY & REMONUMENTATION

1993

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Gratiot County Remonumentation Program

GRATIOT CO. MICH.
 RECORDED

'93 DEC 20 PM 12 21

Janet M. Davis
 REGISTER OF DEEDS

COMMISSION
 For corners in
Gratiot
 (County)

Located In: _____ Corner Code # _____

- | | | | |
|---------------------------------------|-------------------------|------------------------|------------------------|
| 1. Public Land Survey | Sec. 36 | T <u>11</u> R <u>4</u> | <u>M-13, SE Corner</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on October 15, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- April 17, 1831, R. Clark, Jr., Deputy Surveyor
- Set post corner T11N R3W and R4W
- Black Ash 12" N22°W 28 links
- Black Ash 11" N2-1/2°E 30 links
- November 20, 21, 22 and 23, 1871, D.W. Altenburg, County Surveyor, Book B, Page 133 from Record of Minutes of Survey of Gratiot County Drain Commission
- Old town corner found 2 x 2 oak post 36" S41-1/2°E 64 links
- Stone 10 x 10 x 12 Oak Post 14" N43-3/4°E 54-3/4 links
- S. Oak 5" South 45 links
- Stone 8 x 16 N47-1/2°W 66-3/4 links
- 1879, T.H. Harrod, Surveyor, Book B, Page 281 Record of Minutes of Survey of Gratiot County Drain Commission
- Found 1/2" Pipe 8" below surface
- 18" Oak NE 61.05'
- 1" iron pipe NW 49.95'
- Butternut NE 49.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Accepted as corner. Found 1/2" pipe in mon box 3' North of Centerline Road 555 and 275.88 feet West of N 1/4 Section 1 T10N R4W


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set remonumentation corner in mon box 3' North of Centerline Road.
- Northwest Corner Concrete Headwall N50°W 50.5'
- Southeast Corner Concrete Headwall S40°W 49.5'
- Utility Marker Post S80°E 130.6'
- NW Corner Section 1 T10N R4W West 275.88'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date November 23, 1993

Surveyor's Michigan License No. 30104



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993