

FEB 22 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

GRATIOT CO. MICH.
RECORDED

'95 DEC 20 PM 1 27

Janet M. Davis
REGISTER OF DEEDS

For corners in <u>Gratiot</u> (County)	Located In: Seville Township	Corner Code #
Public Land Survey	Sec. 30 T <u>12</u> N R <u>4</u> W	<u>A-11, SW Corner</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Tingley a field survey on August 1, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 832, Orange Risdon, Deputy Surveyor, GLO Notes
Set Post: 17 links South of Post T12N-R5W
Beech 14" N23°E 32 links
Beech 14" S32°E 77 links
October 1871, D.W. Attenburg, County Surveyor, LA-280
Post 2 x 2
Pine Stump 20" S45°E 16 links
Maple 14" N76-1/2°W 22 links
Old Corner Found
- 874, S.S. Hastings, Deputy County Surveyor, Liber B, Page 199
See Liber B, Page 58
February, 1906, E.W. Redman, County Surveyor, Liber D Page 78
Original Corner Found, Stake and Iron
Maple 3" N84°E 43-1/2 links
Pine Stump 30" S70°25'E 54 links (at heart)
February 1906, E.W. Redman, County Surveyor, Liber C, Page 106 and 107
Original Corner Found Stake and Iron
Maple 3" N84°E 43-1/2 links
Pine 30" S70°25'E 54 links

ACCEPTED BY THE GRATIOT COUNTY SURVEY PEEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11 29 95

W.T.
William Tingley, PS, Chairman



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 3/4" Iron Pipe, 1.5 feet long, 4.5 feet West of Centerline
- Found 28" Silver Maple, believe it to be Redman (County Surveyor) 1906 Witness Tree

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner and Monument Box
- Set Nail and Tag Southside 28" Maple N84°E 28.71 feet (at center of tree)
- Found Nail Power Pole N25°W 40.18 feet
- Found Nail 16" Walnut N30°E 79.27 feet
- Found Nail Power Pole N60°E 27.47 feet
- 1 Feet South of Corner for 25-12-5

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-12, 1995
Surveyor's Michigan License No. 30104