

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 N.R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 Corner Common to Sections 11 & 14

CORNER MONUMENT Fd. 1/2" pipe in approximately Inter. of Fire Lanes (E-W-S).
Added Std. Dept. Mon. (Buried).

DATE MONUMENT PLACED AND WITNESSED 5-9-69

WITNESSES TO CORNER..... 8" R. Pine N 01 W 36.4'



16" W. Pine S 23 W 50.6'

Set Cedar Post Due N 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered during retracement survey in this area. Found 1/2" pipe which fits M.S.H.D. Witness and description as shown in survey notes dated 1938 by S.J.E. Lucas. Norton & Associates, R.L.S., Traverse City have used this corner to subdivide Sec. 11. See PLAT OF SURVEY for additional information.

SURVEYOR'S SEAL

SIGNED *Carl F. Rosen* DATE 5/28/69
REGISTERED LAND SURVEYOR 12028