


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY

T 25 N R 8 & 9 W

DESCRIPTION OF CORNER 1/4 Corner common to Sections 19 & 24  
CORNER MONUMENT Set Std. Dept. Mon. (buried) in approx. ctr. of N-S Co. Road.  
DATE MONUMENT PLACED AND WITNESSED 5-28-69  
WITNESSES TO CORNER.....



12" Oak S 59 W 57.5'

10" R. Pine N 52 W 40.6'

Set Ced. Post Due E 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion between Section corners to N & S. The corner is in line with the South edge of a fire lane to the west.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rover*  
REGISTERED LAND SURVEYOR 12028

DATE

8-8-69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68