

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 8 & 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 24 & 25 19 & 30

CORNER MONUMENT Set Std. Dept. Mon. (Buried)

DATE MONUMENT PLACED AND WITNESSED 5-29-69

WITNESSES TO CORNER..... 12" Red Pine S 54 W 102.4'



14" Red Pine N 54 W 79.2'

Set Ced. Post Due W 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement survey in this area. The corner falls 5' W of the N & S center of an irregular T road intersection; being in line with the average road centerline and split of fences for one mile to the East. The corner also fits the average line of the split of the fences and road centerline for one mile to the South. Also see Plat of Survey.

SURVEYOR'S SEAL

SIGNED

Carl F. Roeder

DATE 8-8-69

REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68