

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 8 & 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 & 30

CORNER MONUMENT Set Std. Dept. Mon. buried

DATE MONUMENT PLACED AND WITNESSED 5-29-69

WITNESSES TO CORNER..... Power Pole (side Nail) N 57 E 49.2'



10" Tamarack N 27 E 139.7'

Set Cedar Post Due W 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement survey in this area. The corner falls in the approximate center of N-S gravel County Road and is in line with line fences to the E & W. The old 1/4 line fences are believed to be a result of a survey of Sec. 25 (25-9) by George Steel, 1895; recorded in County Surveyor's Records, L. 1-P.9.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer
REGISTERED LAND SURVEYOR 12028

DATE

8/8/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68