

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to sections 22 & 23

CORNER MONUMENT Set Std. Dept. Mon. with Cedar guard post at intersection
of fire lanes N-S-W

DATE MONUMENT PLACED AND WITNESSED July 1969

WITNESSES TO CORNER.....



6" W. Pine S 30 E 16.6'

5" R. Pine N 40 W 18.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set during a retracement survey in this area. The corner was established by single proportion between found section corners to N & S.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer

DATE

8-8-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR **12028**

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68