


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY

T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 - 10
CORNER MONUMENT Set Std. Dept. Non buried 0.3', along with white crockery in hole.
DATE MONUMENT PLACED AND WITNESSED 11-10-70
WITNESSES TO CORNER.....



14" Red Pine	S 34 E	46.5'
22" Oak	N 51 E	74.7'
AND C.Line E-W sand trail	Due S	7.5'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. Corner was established equidistant and on line between Sec. corners to East and West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Rosen
REGISTERED LAND SURVEYOR 12028

DATE

11-17-70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68