

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY
T 25 N R 9 W


DESCRIPTION OF CORNER See. corner common to Sections 3-4-9-10

CORNER MONUMENT Set Std. Dept Mon. buried 0.5'

DATE MONUMENT PLACED AND WITNESSED 11-10-70

WITNESSES TO CORNER.....

8" Maple 5-clump	N 73 E	91.0'
18" Oak	S 20 E	188.5'
N-S Fn. Remains	Due W	33'
AND Int. of dirt trail N-S-E-W	S 80 E	15'



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. This corner was established by double proportion to U.S. for one mile N-W-E and 1/2 mile S. The corner falls 33' East of very old N-S fence remains. The dirt trail intersection in this area is irregular.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer
REGISTERED LAND SURVEYOR

DATE

11-17-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing