

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 4 & 9

CORNER MONUMENT Set Std. Dept. Mon (buried 0.5')

DATE MONUMENT PLACED AND WITNESSED 11-10-70

WITNESSES TO CORNER..... 28" Maple N 14 E 34.4'



17" Maple N 50 W 39.5'

In Cline E-W sand trail

E-W Fence Due S 23.0'

AND Old Fence corner Due North 23.0'  
Fence E-W-N

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established in the approximate center of E-W County Trail road which fits the split of the old E-W ROW fences to E & S, and is in line with old line fence to the North. This position also fits an old 1/8 line fence to the West which fits the split of the section line for 1/2 mile to the West. A corner by single proportion would have fallen 10 ft. N and 4 ft. E. We want with the corner as established by old occupancy since the fences appear to have been set as the result of an old survey, of which we cannot now find any record.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rosen*  
REGISTERED LAND SURVEYOR 12028

DATE

11-17-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing