

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES


LAND CORNER RECORD

GRAND TRAVERSE COUNTY

T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 & 4
CORNER MONUMENT Set Std. Dept. Mon.
DATE MONUMENT PLACED AND WITNESSED 11-10-70

WITNESSES TO CORNER.....	<u>6" Maple (cluster-4)</u>	<u>N 80 W</u>	<u>24.7'</u>
	<u>6" W. Pine</u>	<u>N 70 E</u>	<u>27.0'</u>
	<u>5" Oak</u>	<u>S 45 E</u>	<u>73.0'</u>
	<u>CTR. N-S- Co. Trail Rd</u>	<u>Due W</u>	<u>8'</u>
AND	<u>Old Pa. remains West</u>	<u>Due N</u>	<u>2.5'</u>



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established on line and at a prorated distance to U.S. between section corners to North and South. Our distance North from the Section corner to the South fits the record distance as shown in Old County Surveyor records at Register of Deeds Office, L.I., P.S, no name or date.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Roer
REGISTERED LAND SURVEYOR 12028

DATE

11-17-70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing