

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 & 3

CORNER MONUMENT Set Std. Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 11-10-70

WITNESSES TO CORNER..... 8" Hemlock S 30 E 44.6'



8" Oak (twin) N 79 E 27.0'

10" Hemlock S 70 W 64.1'

AND CLine of N-S trail Due W 12'

Fence West Due N 28'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established on line and at a prorated distance to U.S. between section corners to North and South. Although there is a N-S trail road with old ROW fences, there does not seem to be any pattern to the fences whereby the corner could have been set by old occupancy. Search of old survey records does not reveal any surveys of record in Sec. 2 or 3 that would help establish this 1/4 corner.

SURVEYOR'S SEAL

SIGNED

Carl F. Rose
REGISTERED LAND SURVEYOR

12028 DATE

11-17-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing