


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY  
T 25 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sectbns 2-11  
CORNER MONUMENT Found 1" square iron, left in place  
DATE MONUMENT PLACED AND WITNESSED 11-12-70  
WITNESSES TO CORNER.....

19" Maple	S 37 E	44.4'
17" Maple	S 02 E	40.4'
Old Fence Cor. 1.5' E & 33' South (Fence E-W-S)		
Old Fence line North	Due E	1.5'
C.Line E-W County Rd	Due S	1.5'
AND		
Old N. ROW Fence	Due N	25'



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement in this area. The corner fits survey data and witness of Section 2, by E. P. Waterman in June 1909. See old survey records at County Courthouse, L.2 - P.364, and L.5 - P.126.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rosen*  
REGISTERED LAND SURVEYOR 12028

DATE

11-19-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing