

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>25</u> N. <u>9</u> R. <u>W.</u>	<u>E-12, F 11</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on MAY 21, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 E-12 RECOV. 2" PIPE IN SQ CONC BASE (BURIED) IN FIRE LANE INTERSEC. N-S-E-W (M. SCHAAF 1938±); FOR W 1/4 COR OF SEC 33.
 F-11 RECOV M. SCHAAF (1938±) 2" PIPE IN E EDGE OF MARSH FOR N 1/4 COR OF SEC. 33. FITS U.S. (G.L.O.) LINE NOTES TIE TO MARSH. (JUST INTO MARSH 65 LINKS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>E-12 FD 2" PIPE W/CONC BASE IN SAND RD INTERSEC. RAISED W/1" X 12" PIPE W/RLS CAP. 16" TRIP OAK N46°E 109.2' 9" CHERRY S60°W 55.6' 9" J PINE N40°W 28.1' SET CED POST W/LOC TAG. S45°E 40'</p>	<p>F-11 FD 2" PIPE & ADDED CED POST W/LOC TAG. 22" TRIP OAK N30°E 44.2' 16" OAK N60°E 30.5' 16" TW W PINE (BLAZED DEAD STUB OF TWIN) S74°E 49.0'</p>
--	--

SIGNED BY Carl F. Roser 02-11-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ FIFE LAKE TWP.
 GRAND TRAVERSE COUNTY

