

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 9 W.	G-12
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION 33	T. 25 N. R. 9 W.	**195.37' S OF F-12
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on MAY 21, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on MAY 21, 1984, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-12 RE-ESTAB E 1/4 COR OF SEC 33 ON LINE & DBL (E.D.M.) DIST ACROSS FD WILCOX 1/8 COR & SEC COR TO S. WILCOX FD SE OF SEC 33 & RE-ESTAB E 1/4 OF SEC 33 PER 1939± M.S.H.D. STA & ALIGN ON U.S. 131. MSHD FD 2" PIPE IN CONC IN FIRE LANE INTERSEC; SAID 2" PIPE IN CONC NO DOUBT BY M. SCHAAF 1938±. WILCOX'S SET R.R. SPK WAS ON ITS SIDE WITH ONLY ONE OF THEIR WITS LEFT THAT WAS RELIABLE. A 3/8" REROD IS 0.3'N (14" DEEP) OF OUR REROD AND ANOTHER 1" X 4" IR IS 0.1'S & 0.3'W OF OUR REROD.
** ESTAB POINT ON N-S 1/4 LINE OF SEC 33 & ON N EDGE OF E-W DYKE (5/8 X 34" REROD); S00°25'32"W, 195.37, FROM CTR OF SEC 33 AS RECOVERED, MONUMENTED & RECORDED BY RLS, BOB MITCHELL. MITCHELL RECOVERED REMAINS OF BOTH GEO STEELE 1874 B.T.S TO STEELES CTR OF SEC 33 (NOW IN WALTON POND).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 FD R.R. SPK & OTHER IRONS; REPLACED W/ 5/8" X 24" REROD w/RLS CAP. (NEWER) T. POLE N50°E 25.27 P. POLE S20°E 34.15 (WILCOX) 11" OAK S18°W 52.68 28" OAK S70°E 90.62 CTR U.S. 131 WEST 71.4'±	DROVE 5/8" X 34" REROD & POURED CONC AROUND & DROVE STL. FN POST ALONGSIDE. 6" W BIRCH N74°W 4.68 8" OAK S82°W 34.99 CTR OF SEC 33 PER B. MITCHELL SURVEY N00°25'32"E 195.37
--	--

SIGNED BY Carl F. Roser 02-11-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)
FIFE LAKE TWP.
GRAND TRAVERSE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____