

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 25 N R 10 W  
R 11 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 & 36

CORNER MONUMENT Found 1" Pipe. Added Std. Dept. Mon & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 7-2-70

WITNESSES TO CORNER..... 12" Twn. Maple N 72 W 95.4'



6" Twn Ironwood S 12 W 86.7'

12" Maple S 70 E 230.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found 1" Pipe as set by E. P. Waterman in Survey of S. 31. See County Survey Records, L.2, P.452, dated Dec. 1913. Waterman had the original Govt. Corner. The corner falls 16' N of fence remains West and 7'+ W. of N-S fence remains.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roer*

DATE

7-17-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68