


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERS COUNTY

T 25 N R 10 & 11 W

DESCRIPTION OF CORNER Sec. corner common to Sections 25-30-31-36
CORNER MONUMENT Set Std. Dept. Mon. (buried 0.5') in road
DATE MONUMENT PLACED AND WITNESSED 7-2-70
WITNESSES TO CORNER.....



11" B. Cherry N 11 E 105.1'
20" Maple S 42 W 111.62'
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found 5/8" rod and large chunk of iron buried in road. Corner falls near N Edge of E-W dirt road and in line with approximate center of dirt road to N., and in line with old line fence to S. Corner fits Survey of S-31 by E.P. Waterman as recorded at Deed Office in Liber 2, Page 452, dated Dec. 1913.

SURVEYOR'S SEAL

SIGNED

Carl F. Rover
REGISTERED LAND SURVEYOR 12028

DATE 7-17-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68