

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


GRAND TRAVERSE COUNTY  
T 25 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 30 - 31

CORNER MONUMENT Set Std. Dept. Mon buried 0.8' in Road

DATE MONUMENT PLACED AND WITNESSED 7-2-70

WITNESSES TO CORNER..... New Conc. Sub'n Mon. Due S. 33.0'



22" Maple N 38 W 38.3'

16" Maple N 62 W 104.6'

AND

Set Tag on Ced. Fn. Post Due N 28.7'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found three large stones in a vertical pit as described by E. P. Waterman, deceased County Surveyor, in County Survey Records at Register of Deeds, Liber 2, Page 452, dated Dec. 1913.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rover*  
REGISTERED LAND SURVEYOR 12028

DATE 7-17-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68