

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 10 W. ●	I-10; I-9; J-9; K-9
2. PROPERTY CONTROLLING IN SECTION--	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION--	T. N. S. R. E. W.	
4. LOT NO....., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCTOBER 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. CONTINUED:

<p style="text-align: center;">XX</p> <p style="text-align: center;"><u>J-9</u></p> <p>FOUND 1/2" BOLT W/NUT</p> <p>*35" MAPLE N9°E 50.83'</p> <p>*28" MAPLE N48°W 58.28'</p> <p>34" MAPLE S63°E 98.78'</p> <p>FN COR (FN S&W) SOUTH 35'±</p> <p>*: E.H. Allyn 1905 B.T.'s</p>	<p style="text-align: center;"><u>K-9</u></p> <p>FOUND 1/2" IRON RAISED W/1" X 12" PIPE (FLUSH)</p> <p>**FN POST (GATE POST) N40°E 44.13'</p> <p>**1" WHITE PINE S42°E 60.1'</p> <p>**P. POLE S37°E 38.37'</p> <p>**COR FN POST (FN W&S) S45°W 43.85'</p> <p>FD ROD W/RLS CAP #12165 S10°W 33.07' (FLUSH W/GROUND)</p> <p>**WILCOX WITS.</p>
---	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-10 RE-SET 1/4 COR TO SEC'S 26 & 27 PER RLS, GLEN DELAMATER'S WITS. AS RECORDED PER ACT 74 IN LIBER 2, PAGE 380. IRON HAD APPARENTLY BEEN GRADED OUT. BELIEVED TO BE PERPETUATION OF 1905 E.H. ALLYN'S CORNER.

I-9 FD 1" PIPE IN APPROX. CTR OF E-W B. TOP RD & N-S GRAVEL ROAD. FD & USED BY RLS, GLEN DELAMATER & OTHERS. BELIEVED TO BE A PERPETUATION OF 1905 E.H. ALLYN CORNER.

J-9 FD & ACCEPTED 1/2" BOLT IN APPROX. CTR OF E-W B. TOP ROAD. FITS TWO LARGE (NOW) 1905 E.H. ALLYN WITS.

K-9 FD 1/2" IRON AS PREVIOUSLY RECORDED PER ACT 74 BY RLS, J. WILCOX. BELIEVED TO BE PERPETUATION OF SEC. COR. AS PREVIOUSLY RECORDED BY SURVEYOR E.P. WATERMAN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;"><u>I-10</u></p> <p>DROVE 5/8" X 3" RE-ROD W/RLS CAP (BURIED .5)</p> <p>**4" JACK PINE EAST 40.20'</p> <p>**8" MAPLE (CLUMP) S75°W 35.63'</p> <p>**9" RED PINE N50°W 64.88'</p> <p>SET CEDAR POST W/LOC EAST 33'</p> <p>TAG</p> <p>CTR N-S ROAD WEST 4'±</p> <p>** = G. DELAMATER WITS.</p>	<p style="text-align: center;"><u>I-9</u></p> <p>FD 1" X 5" PIPE OVER ANOTHER IRON</p> <p>P. POLE S50°W 41.85'</p> <p>7" RED PINE N45°E 83.80'</p> <p>P. POLE S45°E 126.60'</p>
---	---

SIGNED BY Carl F. Roser 6/07/84 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

CHIEF OF SURVLY PARTY

MICHIGAN REGISTERED LAND SURVEYOR

