

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Grand Traverse Co. _____
(County) Located In Corner Code #

1. Public Land Survey	T _____	R _____			
	T _____	R _____			
2. Property Controlling in Section	S 34	T 25N	R 11W		12
	S 34	T 25N	R 11W		11
3. Miscellaneous Property in Section	S _____	T _____	R _____		
	S _____	T _____	R _____		

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 29, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
12 - None 11 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
12 - CS 1/16 corner, Sec. 34, T25N, R11W. - Set stamped 2" aluminum cap on 5/8" x 34" rebar per standard BLM procedure. Corner of fence S & W is 3' W. and 10.5' N.
11 - SW 1/16 corner, Sec. 34, T25N, R11W. - Set stamped 2" Aluminum Cap on 5/8" x 34" rebar per standard BLM procedure. Fd. a pipe N84° 55' E 5.2'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
12 - 2" Aluminum Cap stamped CS 1/16 S34
N72°W 84.51' to set N & T in S. side 9" Maple
N58°W 36.20' to set N & T in S. side 11" Maple
N02°E 117.15' to set N & T in E. side 12" Maple
S36°E 176.17' to set N & T in S. side 8" Fir
Set Blue Carsonite Post with Loc. tag 1' NE
11 - 2" Aluminum Cap stamped SW 1/16 S34
N08°W 84.20' to set N & T in E. side 7" Basswood
N56°E 20.66' to set N & T in N. side twin 5" Cherry
S22°E 34.32' to set N & T in E. side 8" Elm
N89°W 61.05' to set N & T in S. side triple 6" Cherry
Set Blue Carsonite Post 1' NE

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/25/2004