

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 11 W.	G-13; H-13; I-13
2. PROPERTY CONTROLLING IN SECTION	34, T. 25 N. R. 11 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	, T. S. R. E. W.	
4. LOT NO.	, RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on April 22, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~

C. (continued) 16  
 Set 1"x36" pipe (buried 0.5') in county road  
 9" Tamarack N32°W 112.90'  
 8" W. Pine S13°W 56.56'  
 8" W. Pine S23°E 94.80'  
 Set cedar post w/loc. tag Due N 33'  
 Center E-W dirt road Due N 6'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-13 Restored corner on split of ROW fences to E. and W. and in line with fence to N. and S.
- H-13 Recovered plow point in line with fence to N.
- I-13 Restored corner on straight line through S½ and SW corner of Sec. 34, and at double the distance from S¼ to E-1/16 corner (fence corner; fence N. & W.).
- 16 Restored corner per standard B.L.M. instructions, which falls in line with old fence to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13	H-13	I-13
Set std. Wexford Co. mon. (buried)	Found plow point, added std. Wexford Co. mon. (buried)	Set std. Wexford Co. mon. and cedar post w/loc. tag
16" Maple N50°W 135.31'	12" Cherry N25°E 101.00'	5" Maple N12°W 24.2'
33" Cherry N06°W 102.82'	8" W. Pine S11°W 137.09'	8" Maple S76°W 26.9'
Center E-W Co. Rd. Due S 3'	4" W. Pine S59°E 64.90'	4" W. Pine S29°E 17.1'
Set cedar post w/loc. tag Due N 25'	Set cedar post w/loc. tag Due N 33'	8" Twn. Maple N30°E 19.2'
	25" Oak S35°E 25.3'	

SIGNED BY Carl F. Roser DATE 7-3-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



**MAYFIELD Twp.**  
**GRAND TRAVERSE COUNTY**

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_