

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 ^{N.} <input checked="" type="radio"/> R. 11 ^{W.} <input checked="" type="radio"/>	H-8; H-9
2. PROPERTY CONTROLLING IN SECTION _____	22, T. 25 ^{N.} <input checked="" type="radio"/> R. 11 ^{W.} <input checked="" type="radio"/>	12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} <input type="radio"/> ^{S.} <input type="radio"/> R. _____ ^{E.} <input type="radio"/> ^{W.} <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 19, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-8 Recovered center of Section 22 per survey by E. P. Waterman, dated 1908 & 1909, Liber 2, page 324.
- H-9 Restored 1/4 corner from found 1/16 corner and center of Section to north, per E. P. Waterman survey date 1908 & 1909, Liber 2, page 324.
- 12 Recovered S 1/16 corner on N-S 1/4 line, Section 22, per survey by E. P. Waterman, dated 1908 & 1909, Liber 2, page 324.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-8	H-9	12
Fd. 1 1/2" pipe, added cedar post w/location tag	Set DNR monument (buried)	Found 1" sq. top iron shaft
7" R. Pine S46°E 44.00	20" Maple S18°E 41.15	9" Maple N63°E 17.40
5" R. Pine N81°E 44.30	12" Tr.B. Cherry Due S 13.42	8" Maple S26°E 23.00
8" Maple N26°W 48.48	6" R. Pine N32°W 37.55	8" Maple S66°W 37.60
9" Maple N62°W 63.00	6" W. Pine N61°W 51.25	in old N-S-E-W fence lines
in old N-S fence row	Set ced. post w/loc. tag	set post w/location tag
	Due N 33.0	Due N 10'


SIGNED BY Carl F. Roser DATE 7-3-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____



MAYFIELD Twp.
GRAND TRAVERSE COUNTY