

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 ^{N.} <input checked="" type="radio"/> R. 11 ^{W.} <input checked="" type="radio"/>	C-12; D-12
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. 25 ^{N.} <input checked="" type="radio"/> R. 11 ^{W.} <input checked="" type="radio"/>	12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} <input type="radio"/> ^{S.} <input type="radio"/> R. _____ ^{E.} <input type="radio"/> ^{W.} <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 22, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-12 Restored corner on straight line through center and E $\frac{1}{4}$ of Section 32, and at proportionate distance to E. H. Allyn distance; see Liber 2, page 266, 1906 & 1907.
- D-12 Recovered buggy axle for center of Section 32, in line with fence to N & S per E. H. Allyn survey of Section 32; Liber 2, page 266, 1906 & 1907.
- 12 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	C-12	D-12		12
Set railroad spike		Fd. buggy axle (buried 1') added		Set 1"x36" pipe
cedar guard post N70°E 40'		cedar post w/location tag		7" Maple N47°W 45.3
Center N-S b'top road (M-37)		9" Maple S02°W 143.53		8" Maple S61°W 38.1
Due E 3'		24" Maple S72°W 114.72		24" Maple S19°E 67.7
		Center E-W sand road Due S 15'		Set ced. post w/loc. tag
				Due E 33'
				Center N-S sand road
				Due E 6'

SIGNED BY Carl F. Roser DATE 7-3-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

MAYFIELD TWP.
GRAND TRAVERSE COUNTY