

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>25</u> <sup>N.</sup> <u>11</u> <sup>W.</sup>	<u>C-9; C-10; D-9; E-9</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ <sup>N.</sup> <sup>S.</sup> R. _____ <sup>E.</sup> <sup>W.</sup>	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ <sup>N.</sup> <sup>S.</sup> R. _____ <sup>E.</sup> <sup>W.</sup>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 1, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration**

C. (continued) E-9  
 Found 1/2" rod, added DNR mon. & cedar post w/loc. tag  
 8" Poplar N15°E 38.55  
 6" W. Pine S85°E 74.62

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- C-9 Accepted corner by RLS Verba which fits old surveys in area of record.
- C-10 Accepted corner by RLS Verba which fits old surveys in area of record.
- D-9 Found concrete monument w/rerod by Wilcox & Erickson per old E. P. Waterman survey. Corner falls in old E-W fence.
- E-9 Accepted 1/2" rod with RLS cap, by Wilcox & Erickson which fits old E. P. Waterman survey of record.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-9	C-10	D-9
Fd. PK, replaced w/3/4"x10" bolt w/washer	Fd. PK, replaced w/3/4"x10" bolt w/washer	Added DNR monument & cedar post
7" B. Cherry S60°W 71.95	14" hemlock S61°W 60.35	14" Maple N08°E 143.0
4" R. Pine N71°W 57.37	18" W. Pine N26°W 108.55	18" Maple N56°E 150.3
set cedar post w/loc. tag Due E on center N-S b.top 33'	12" W. Pine N33°E 114.55	14" Tw. B. Cherry S63°E 152.1
road (M-37)	Set cedar post w/loc tag Due E 33'	
	Centor N-S b.top road (M-37) W. 0.5'	

SIGNED BY Carl F. Roser DATE 7-3-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

