

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 25 N.R. 12 W


Grand Traverse COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19-20-29-30

CORNER MONUMENT Drove 1" x 2 1/4" pipe, only

DATE MONUMENT PLACED AND WITNESSED April 18, 1966

WITNESSES TO CORNER.....



7" H. Maple S 86 W 66.8

10" H. Maple S 40 W 49.2

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey of Section 20. Set corner in line with old fence from north, which conforms with center of old roads east and west, and checks 1/4 line fence east. A large rock at this position may have been intended to mark the corner in an earlier survey. No other evidence.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR #10068

DATE April 21, 1966