

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 25 N. R. 12 W


Grand Traverse COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17, 18, 19 and 20

CORNER MONUMENT Set 1" pipe with 1/4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 18, 1966

WITNESSES TO CORNER.....



7" S. Maple S 18 E 14.7'

12" R. Oak N 37 W 42.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between corners 1/2 mile east, 1/2 mile west, 1 mile south and 1/2 mile north. No evidence of Hemlock USBTs.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE April 21, 1966
REGISTERED LAND SURVEYOR #10068