

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 12 W. ●	B-1
2. PROPERTY CONTROLLING IN SECTION 18 _____	T. 25 N. R. 12 W. ●	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 5, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1** Previous Department corner of record (1966-Shadko); see PAS #28-23, Survey Project #70-33.
- 1 Found and accepted 1" square-head bolt (buried) in N-S sand road. Corner fits Sec. 18 subdivision by E. H. Allyn, 1904, Liber 3, pages 308 and 309.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1		1
Fd. (Dept.) Shadko mon. in mon. box.		Fd. & accepted 1" sq. head bolt (buried 0.4)
17" Oak N12°W 39.38		12" Oak N73°E 40.62
18" R. Pine S50°W 69.17		7" Oak S45°E 62.72
16" R. Pine S35°E 34.87		9" Oak S36°W 59.21
Set cedar post w/loc. tag S. 33'		☉ sand N-S Rd. is Due W. 3'±
Fd. Shadko mon. for S¼ of Sec. 31		☉ sand Rd. to E is Due S. 15'±
N89°47'W 236.13		Set cedar post w/loc. tag E. 33'
☉ E-W b'top rd. Due S. 1'±		

SIGNED BY Carl F. Roser 4-8-80

DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_  
CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY  
GRANT TOWNSHIP