

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 12 W. ●	C-1
2. PROPERTY CONTROLLING IN SECTION 9.....	T. 25 N. R. 12 W. ●	3
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 5, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1** Previous Dept. corner of record (1966-Shadko); see PAS #28-23, Survey project #70-33. Corner is in line with center of blacktop road looking W and 10'± W of center of blacktop road looking S.
- 3** Fd. and accepted iron for 1/8 corner as set by E. P. Waterman survey in 1909 (\*Fd. one Waterman witness 18" pine N35°W 5.7'). Iron falls in old fence corner, fences N and E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	C-1		3	
Fd. Dept. mon by Shadko & added ced. post		Fd. 1" square iron; added cedar post		
21" Oak	S85°W 13.15	w/loc. tag		
14" Oak	N16°W 55.90	7" Oak	N28°W	16.71
12" W. Pine	S47°E 42.49	8" Oak	N19°E	16.16
Q sand trail N'y E	32'±	7" Maple (twin)	S30°E	36.00
Fd. Shadko mon. for SE Sec. 31		*20" Pine stp. w/scribe	N28°W	5.6
	N89°38'W 236.13			


SIGNED BY Carl F. Roser 4-8-80 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY  
 GRANT TOWNSHIP