

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 12 W.	C-9; E-4; E-5	
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.		
4. LOT NO., RECORDED PLAT.....			
5. PRIVATE CLAIMS.....			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-9** Fd. 1" pipe for SW cor. Sec. 20 as reestab. by R.L.S. K. J. Ostling (Dept. survey 1966) in line w/fence N, & avg. ctr. of irregular trail rd. to E & W. Corner is just N of traveled rd. at corner, w/large stone on N side of pipe.
- E-4** Fd. round conc. mon. probably by Perla, for E $\frac{1}{4}$ cor. Sec.8. seems to fit survey of Sec. 8 by J. J. Hubbell in 1901 for Plat of Karlin & subsequent surveys by E. P. Waterman in 1912 and C. P. Tuller in 1920.
- E-5** Reestab. SW cor. Sec. 9 by doubling over fd. 1/8 cor. and fd. $\frac{1}{4}$ cor. to N. This fits split-up of SE $\frac{1}{4}$ of Sec. 8 by Hubbell for Plat of Karlin in 1901 & Perla's survey of NE $\frac{1}{4}$ SE $\frac{1}{4}$ Sec. 8 in 1969 reasonable. Fd. 1 $\frac{1}{2}$ "x1" solid iron bar N39 \circ 56'E 79.0'; can find no record of this iron & therefore could not accept for sec. corner (way out of position).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9	E-4	E-5
Fd. 1"x2' pipe; replaced w/DNR mon. & set cedar post.	Fd. round conc. mon. & added cedar post w/loc. tag.	Set DNR Mon. w/cedar post.
10" Maple Due N 51.33	13" R. Pine N62 \circ W 17.75	7" Beech N34 \circ E 11.8
12" Maple Due W 67.17	12" R. Pine S52 \circ W 4.07	4" Oak N73 \circ W 19.2
16" Maple S43 \circ W 49.36	11" R. Pine S35 \circ E 15.85	4" Maple S48 \circ E 23.5
Q. E-W Trail South 13'±		


SIGNED BY Carl F. Roser 4-8-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY GRANT TOWNSHIP