

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 25 N. R. 12 W.	E-6; F-5; F-6
2. PROPERTY CONTROLLING IN SECTION 16.	T. 25 N. R. 12 W.	9
3. MISCELLANEOUS PROPERTY IN SECTION	T. 1 S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 14, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

= * * * * * =

C. (continued)

- 9
- Drove 5/8"x36" rerod w/RLS cap & set cedar post w/loc. tag
- | | | |
|------------------|----------|-------|
| 21" Oak | N66°W | 18.9 |
| 7" Maple | N36°E | 14.0 |
| 11" Maple | S75°E | 25.8 |
| *Fd. old 2" pipe | N09°18'W | 13.87 |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-6** Reestablished W $\frac{1}{4}$ corner Sec. 16 single proportion between fd. SW S-16 (C.P. Tuller pipe) and reestablished NW corner S-16.
- F-5** Reestablished N $\frac{1}{4}$ corner S-16 equidistant & on line between sec. cor. to E & W.
- F-6** Set center of Sec. 16 at intersection of $\frac{1}{4}$ lines. Corner is 1'± E of old B-W fence, N-S, posts all down.
- 9** Set 1/8 corner per std. BIM instructions. Corner falls 2'± W of old N-S fence. Fd. 2" pipe at old fn. inter., fns. E-W-S (B-W, mostly down), see tie * in wits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6	F-5	F-6
Set DNR Mon. & Cedar Post	Set DNR Mon. & Cedar Post	Drove 5/8"x36" rerod & set cedar post w/loc. tag
12" Oak N18°W 50.4	6" W. Oak S73°W 53.9	5" Maple N55°W 29.1
12" Oak N55°E 47.0	5" Maple N56°E 55.3	12" W. Oak N54°E 48.7
10" Oak S13°E 59.9	8" W. Oak S59°E 39.8	19" W. Oak S03°E 24.0
N-S Random line Due W 0.1'		*Fd. old 2" pipe N03°57'W 21.2

SIGNED BY Carl F. Roser 4-8-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY
GRANT TOWNSHIP