

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. 25 N. R. 12 W.	H-5; H-6; I-7
2. PROPERTY CONTROLLING IN SECTION 16	T. 25 N. R. 12 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION-----	T. S. R. E. W.	
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 14, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and or subsequent restoration:~~

C. (continued)

15

Drove 5/8"x36" rerod w/RLS cap (buried).
 12" Maple N45°E 34.0
 8" Maple N10°W 65.4
 5" R. Pine S08°E 22.6
 Set ced. post w/loc. tag Due W 16.5
 *Fd. old 2" pipe S82°42'W 11.96

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-5 Fd. & accepted old cor. fn. post (king post) w/old fn. remains E-W-S. E.P. Waterman 1912, L. 2, p. 90 of old Co. Sur. Rec. calls for "large cedar fn. post where 1/4 post was - one US wit. here yet".
- H-6 Fd. stone w/+ on top & sev. smaller rocks under it per Waterman notes of 1912 & Allyn's notes of 1903 who fd. Slawson's old stake for ctr. of Sec. 15. Stone is on E side old cor. fn. post w/WW fence to S & W & b'wire on trees & some posts to N & E.
- I-7 Fd. 3/4" pipe for SE corner of Sec. 15
- 15 Set 1/8 cor. per std. BLM Instr. Fd. Tuller's *2" pipe too far W to accept for proper 1/8 cor 1/8 Cr. as estab. this survey (5/8"x36" rerod) falls in ctr. two-track trl.rd. to S. Main sand trl. (NW-SE) is 155'± to N. Tuller pipe (noted in wit-item C) has old fn. mostly dn.,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner running S of /it.

	H-5	H-6	I-7
Fd. ced. cor. post (down) & repl. w/DNR Mon. & cedar post.	Fd. stone w/cross (0.8x0.6) & added ced. post w/loc. tag.	Found 3/4" pipe.	
6" Maple N26°W 30.4	9" Maple N77°W 29.1	20" Maple N65°W 104.27	
8" Maple N33°E 42.3	12" Maple S18°W 15.9	in E-W b'top road N75°E 96.56	
9" Oak S45°E 44.7	9" Maple N04°W 20.5	in E Gravel rd. N & trl. rd. S	
20" Old pine stp. S22°E 33.8			
w/blaze			


SIGNED BY Carl F. Roser 4-8-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY
GRANT TOWNSHIP