

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 12 W.	A-3; A-4; B-3; C-3
2. PROPERTY CONTROLLING IN SECTION.....	7, T. 25 N. R. 12 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO.	RECORDED PLAT.....	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 19, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A - Description of original monument and accessories and re-subsequent restoration:~~

C. (continued)

C-3	1
Fd. conc. mon. & added cedar post w/loc. tag.	Drove 5/8"x36" rerod w/RLS cap & set cedar post w/loc. tag.
13" Oak S36°E 9.82	4" Oak S26°E 65.6
13" R. Pine N60°W 30.53	4" Oak S53°E 65.5
17" Oak N35°E 60.71	8" Pincherry N22°E 108.8
☉ of winding trail-N. 15'±	E-W Random North 7'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-3** Fd. & accepted conc. mon. for NW corner Sec. 7 as set by Perla & Stout in 1965 survey Sec. 6.
- A-4** Set DNR mon. single proportion to U.S. for W $\frac{1}{4}$ corner Sec. 7.
- B-3** Fd. & accepted conc. mon. as set by Perla & Stout in 1965 survey of Sec. 6 (they set $\frac{1}{4}$ corner pro-rated to U.S.).
- C-3** Fd. & accepted conc. mon. for SE corner Sec. 6; fits Perla & Stout survey of Sec. 6 and C. O. Carver survey of NW $\frac{1}{4}$ Sec. 8, 1926±, L. 7, page 242.
- 1** Set 1/8 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	A-4	B-3
Fd. conc. mon. & added cedar post w/loc. tag.	Set DNR Mon. & Ced. Post.	Fd. Conc. mon. & added cedar post w/loc. tag.
4" W. Pine N78°E 30.8	5" W. Pine S02°W 12.0	22" Maple S38°E 19.6
9" Maple S47°E 88.6	6" Oak N22°W 40.5	10" Cedar S02°E 59.3
6" Trpl. Maple S09°E 106.2	16" Oak N64°E 31.8	8" Maple S58°W 50.5
☉ N-S Trl. (RR grade) East 12'±	Ctr. N-S trl. rd. (old RR grade) W'y 250'±	13" Maple N37°W 35.6
	Old N-S Trail East 70'±	

SIGNED BY Carl F. Roser 4-8-80

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GRAND TRAVERSE COUNTY
GRANT TOWNSHIP