

✓

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY
T 26 N R 9 W


DESCRIPTION OF CORNER Sec. corner common to Sections 27-28-33-34

CORNER MONUMENT Set Std. Dept. Mon. & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 8-31-70

WITNESSES TO CORNER.....

22" R. Pine	N 65 W	134.9'
9" Maple	S 35 W	79.2'
Centerline E-W Dirt Road	SOUTH	32'
AND N End of 12" CMP	S 18 E	22.3'



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was set by Double proportion to U.S. for one mile N-S-E-W. The corner fits U.S. distance South 1135', to stream crossing.

SURVEYOR'S SEAL

SIGNED Carl F. Borer DATE 8-31-70
REGISTERED LAND SURVEYOR 12020

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing