

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 9 #

Grand Traverse COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2-3-10-11

DESCRIPTION OF CORNER MONUMENT Left 1 1/2" pipe in place.

WITNESSES TO CORNER

* 14" R. Pine - N60W - 25.5 feet

8" Double W. Oak - S43W - 40.1 feet

5" R. Pine - S16E - 48.5 feet

* Probable Allyn witness of 1906.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in Section 3. Found a 1 1/2" pipe in place at intersection of firelines E-W-S. A 1/2" iron bar is 4" north of pipe. Corner is thought to perpetuate the government corner as identified and restored by E.H. Allyn in 1906. Distance north to Allyn's 1/8 corner checks acceptably, and a Red Pine NW which could answer for His NW witness, although the distance is 25.5' instead of 27.5'.

Corner was placed and witnessed June 25, 1959.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

DATE 6/29/59