

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 R 8 E

DESCRIPTION OF CORNER S 1/16 corner common to Sections 26 & 27

CORNER MONUMENT Set 1" x 36" Pipe with Cedary Guard Post & location Tag

DATE MONUMENT PLACED AND WITNESSED 8-28-70

WITNESSES TO CORNER..... 6' B. Cherry N 63 E 33.1'



7' Tamarack S 82 E 44.5'

Ctr. Old N-S Twp. Rd. Grade DUE E 10'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established equidistant and on line between 1/4 corner N & Section corner S.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rees*  
REGISTERED LAND SURVEYOR 12028

DATE

8-2-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68