

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 34 & 35

CORNER MONUMENT Set Std. Dept. Mon., buried 0.5' in dirt road

DATE MONUMENT PLACED AND WITNESSED 8-28-70

WITNESSES TO CORNER,..... 10' Maple S 29 E 94.7'



14' W. Pine S 42 W 105.1'

Set location tag on N 35 W 41.3'
Corner Fence Post

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a retracement survey in this area. The corner was restored to proper position based on prorated distance to E.P. Waterman measurement on the W. side of Sec. 35, as recorded in his survey of Sec. 35, dated September 1893. Recorded at Register of Deeds in Liber 1, Pages 420 & 421.

SURVEYOR'S SEAL

SIGNED

Carl J. Bean
REGISTERED LAND SURVEYOR 12028

DATE

9-2-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68