


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY
T 26 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 26 & 35
CORNER MONUMENT Set Std. Dept. Mon & Cedar Guard Post
DATE MONUMENT PLACED AND WITNESSED 8-28-70
WITNESSES TO CORNER.....



28' Maple S 02 W 61.8'
40' Ash N 30 W 37.6'
Ctr Old E-W Twp. Road Due N 12' ±
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found large, long, pointed stone, surrounded by stones as called for in E. P. Waterman's survey of Sec. 35, dated Sept. 1893, as recorded in old survey records at Register of Deeds, Liber 1, Page 420 & 421.

SURVEYOR'S SEAL

SIGNED Carl F. Rose DATE 9-2-70
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68