


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY

T 26 N R 9 W

DESCRIPTION OF CORNER Ctr. corner Section 35
 CORNER MONUMENT Fd. Blue Pointed Stone on End surrounded by smaller stones.
 Added 1" x 3/4" Pipe (buried 0.5')
 DATE MONUMENT PLACED AND WITNESSED 7-29-70
 WITNESSES TO CORNER,..... Ctr. L-W Co. road Due S. 3'



Old Cor. Fm Post	Due N.	29'
18 Maple	S 44 W	47.55
AND 24" Maple	S 30 E	35.73

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found above-described stone in line with old fence remains to N & S. L. P. Waterman survey of Sec. 35 in Sept. 1893, as recorded in County Survey Records at Register of Deeds in Liber 1, P-420, calls for Cedar Post & stones. Corner fits the 1893 Sec. Subdivision and is accepted as proper center of Section.

SURVEYOR'S SEAL

SIGNED

Carl F. Roeder

DATE

8-5-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68