

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 6 & 7

CORNER MONUMENT Set Std. Dept. Mon. with Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 12/6/68

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

<u>12" Oak</u>	<u>S 5 W</u>	<u>7.8'</u>
<u>12" Oak</u>	<u>S 85 W</u>	<u>67.2'</u>
AND		
<u>E-W Random</u>	<u>Due N</u>	<u>42.2'</u>

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion between found M.C. to West and set sec. corner to East. There are highly irregular fence remains (no corner post) westerly and northerly from the general vicinity of our 1/4 corner, but I can find no basis to accept these fence remains as a basis of restoring the 1/4 corner.

SURVEYOR'S SEAL

SIGNED *Carl F. Rosen* DATE 1/7/69
REGISTERED LAND SURVEYOR

#12028