

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 18 & 19

CORNER MONUMENT Set Std. Dept. Mon. & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED December 1968

WITNESSES TO CORNER..... 12" Oak S 45 W 61.6'



10" Oak S 10 E 71.3'

SE Cor. Old Conc. Fdn N 10 W 38.2'

AND

Approx. center of E-W Sand Rd., Due S 5.0'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion between found section corners to E & W. Schaaf set a pipe in concrete for a 1/4 corner by (S.P.). We found it 16 feet West of our point and pulled it as it had not been used and accepted.

SURVEYOR'S SEAL

SIGNED Carl F. Boer DATE 1/8/69
REGISTERED LAND SURVEYOR
#12028