

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N. R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 5 & 6

CORNER MONUMENT Set Std. Dept. Mon. with Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 12/6/68

WITNESSES TO CORNER.....



8" R. Pine N 27 W 29.9'

10" R. Pine N 3 E 71.6'

AND

10" Oak S 10 W 5.8'

N-S Random Due E 40.2'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion between section corners to N & S.

SURVEYOR'S SEAL

SIGNED *Paul F. Rosen* DATE 1/7/69
REGISTERED LAND SURVEYOR #12028