

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 23-24-25-26

CORNER MONUMENT Found 1' pipe, left in place

DATE MONUMENT PLACED AND WITNESSED 11-12-70

WITNESSES TO CORNER..... 24' Maple S 62 E 95.0'



24' Maple S 19 W 94.3'

On C.Line Blackp N-S County Road

AND
Ctr.Line of Dirt Road E&W Dur N. 4'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. E. P. Waterman survey of Sec. 26 in April 1894 calls for Cedar stake and stones. County Road Comm. corner data indicates they found a cedar stake. We recovered a pipe which fits Waterman survey of Section 26. Pipe was probably set by Road Comm. when road was blacktopped.

SURVEYOR'S SEAL

SIGNED

Carl F. Rover
REGISTERED LAND SURVEYOR

12028 DATE

11-19-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing