

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY

T 26 N R 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 14-15-22-23


CORNER MONUMENT Set Std. Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 11-9-70

WITNESSES TO CORNER.....

9" Oak	N 68 W	35.4'
15" Oak	S 25 E	31.1'
15" Oak	S 69 E	43.8'

AND
Set at Int. of Dirt trail N-E-E-W



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found Schaaf pipe monument and added Std. Dept. Monument. Schaaf notes (Twp map in back of Govt. notes) indicate he had an original corner here. Corner fits US distance to stream crossing to South and East edge of swamp to West.

SURVEYOR'S SEAL

SIGNED

Carl J. Rauer
REGISTERED LAND SURVEYOR

DATE

11-16-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68