

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 9 W

DESCRIPTION OF CORNER N 1/16 corner common to Sections 25 & 26

CORNER MONUMENT Set 1"x36" Pipe

DATE MONUMENT PLACED AND WITNESSED 11-2-70

WITNESSES TO CORNER..... 5" R. Pine S 57 E 43.2'



5' J. Pine N 54 W 56.0'

C. Line of N-S Blacktop Co. Road DUE EAST 2'

AND in line with old fence line East

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set equidistant and on line between Sec. corner to North and 1/4 corner to South.

SURVEYOR'S SEAL

SIGNED

Carl F. Rosen

12028 DATE

11-9-70

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68